



ભક્તકવિ નરસિંહ મહેતા યુનિવર્સિટી, જૂનાગઢ



Inviting e-Tendering Notice for Providing Mandap Stage and Other Necessary Facilities for 2 Year Rate Contract on Various Govt. Functions at Bhakta Kavi Narsinh Mehta University, Junagadh. (2nd Attempt) (Item Rate on Annual Base)

Tender Fee : Rs. : 2,500/- (D.D.) (Non- Refundable)
E.M.D. : Rs. : 1,35,000 /- (D.D.) (3% of the Estimated cost),)
Security Deposit Rs. : 5 % of contract value (D.D.)

In favour of the **Registrar, Bhakta Kavi Narsinh Mehta University, Junagadh,** for the values as mention above as tender fee (non-refundable in any case)

Tenders to be submitted at :

**Registrar,
Bhakta Kavi Narsinh Mehta University,
Government Polytechnic Campus,
Bhakta Kavi Narsinh Mehta University Road,
Khadia, Junagadh - 362263
Phone No : 0285-2681400**



ભક્તકવિ નરસિંહ મહેતા યુનિવર્સિટી, જૂનાગઢ

Notice Inviting On-Line Tender

Details about Tender: Tender Notice No. 04 of 2026

Department No.	:	Education Department
University	:	Bhakta Kavi Narsinh Mehta University - Junagadh
IFB No. / Tender Notice No.	:	04/2026
Name of Project	:	2 Year
Name of Work	:	Providing Mandap Stage and Other Necessary Facilities for 2 Year Rate Contract on Various Govt. Functions at Bhakta Kavi Narsinh Mehta University, Junagadh. (2 nd Attempt)
Estimated Contract Value(INR)	:	Rs. 45,00,000.00
Period of Completion (in Months)	:	(24) Twenty Four Months
Bidding Type	:	Open
Bid Call (Nos)	:	-
Tender Currency Settings	:	INR
Joint Venture	:	Not Applicable
Rebate	:	Not Applicable
AMOUNT DETAILS		
Bidding Document Fee	:	2,500/-
Bidding Document Fee Payable To	:	Registrar, Bhakta Kavi Narsinh Mehta University - Junagadh
Bid Security / EMD (INR)	:	1,35,000.00
Bid Security / EMD In Favour Of	:	Registrar, Bhakta Kavi Narsinh Mehta University - Junagadh
TENDER DATES		
Bid Document Downloading Start Date	:	Dt. 02/02/2026 from 00:01 Hrs.
Bid Document Downloading End Date	:	Dt. 09/02/2026 upto 18:00 Hrs.
Last Date & Time for Receipt (Submission) of Bids online	:	Dt. 09/02/2026 upto 18:00 Hrs.
Last Date & Time for Receipt (Physical Submission) of Bids in hard copy	:	Dt. 12/02/2026 upto 18:00 Hrs.
Bid Validity Period	:	180 days from last date of uploading bid.
Submission of documents	:	Any documents in supporting of bid shall be submitted in electronic format through online (by scanning etc.) and also in hard copy to the



ભક્તકવિ નરસિંહ મહેતા યુનિવર્સિટી, જૂનાગઢ

		University.
Remarks	:	Tenderer shall submit their offer in electronic format on web site, after digitally signing the same, offers which are not digitally signed will not be accepted.
Tentative Bid Opening Date	:	Dt.13/02/2026 at 12:00 Hrs.
Other Details		
Officer Inviting Bids	:	Registrar, Bhakta Kavi Narsinh Mehta University - Junagadh
Bid Opening Authority	:	Registrar, Bhakta Kavi Narsinh Mehta University - Junagadh
University Address	:	Bhakta Kavi Narsinh Mehta University, - Junagadh
Contract Details	:	

General Terms and Condition

- (1) Contractors Registered in **Experience Contractor of Experience of similar nature of work as described in previous page under topic Submission of document** and above will be permitted to tender. Not more than one tender shall be submitted by a contractor or by a firm of contractors. No two or more concern in which an individual is interested as proprietor and / or a partner shall tender for the execution of the same work if they do so, all such tender shall be liable to be rejected.
- (2) Bidders can download the tender document free of cost from the website.
- (3) Bidders have to submit bid in Electronic format on nprocure website till the Last Date & time for submission mentioned above.
- (4) Bidders shall submit their Pre-Qualification bid documents and other valid certificates with original Tender Fee and EMD in physical form to **Bhakta Kavi Narsinh Mehta University - Junagadh** till the last date of physical submission mentioned above.
- (5) Tender fee & EMD shall be paid along with submission of tender in separate cover. "All the relevant document of tenders as stated here under to be submitted physically will be received only by Registered Post A.D or Speed Post or through courier service addressed to The Registrar, BKNM University, Junagadh, "NO HAND DELIVERY" will be accepted.



ભક્તકવિ નરસિંહ મહેતા યુનિવર્સિટી, જૂનાગઢ

SECTION – A

ACKNOWLEDGMENT

Tender for the work:-

TENDER FEE PAID VIA DEMAND DRAFT NO. _____

DATED _____ RS. _____

EARNEST MONEY DEPOSIT PAID VIA D.D . NO. _____

DATED _____ RS. _____

The undersigned reserves the right to reject any or all tenders without assigning any reasons thereof.

The Tender fee, Earnest Money Deposit will be accepted in form of Demand Draft and **Earnest Money Deposit** of amount as described in tender notice will be accepted in form of Demand Draft of Nationalized **Bank drawn in favor of “The Registrar – BKNM University” payable at Junagadh.**

Signature of Contractor



ભક્તકવિ નરસિંહ મહેતા યુનિવર્સિટી, જૂનાગઢ

	Further Details of this tender are as per under:
1.0	Particulars: As per above list of works
2.0	Downloading Tender Document:
2.1	Bid documents will be available on web site up to Date shown above.
2.2	Bidders wishes to participate in this tender will have to register on web site https://tender.nprocure.com
3.0	Digital Certificate:
3.1	Bidders who wish to participate in online tenders will have to procure / should have legally valid Digital Certificate (Class III) as per Information Technology Act-2000 using which they can sign their electronic bids. Bidders can procure the same from any of the license certifying authority of India or can contact (n) code solutions - a division of GNFC Ltd, who are licensed Certifying Authority by Govt. of India. All bids should be digitally signed, for details regarding digital signature certificate and related training involved the below mentioned address should be contacted:
3.2	(n) Code solutions A division of GNFC 301, GNFC Info tower, Bodakdev, Ahmedabad - 380 054 (India) Tel: +91 26857816/17/18 Fax: +91 79 26857321 E-mail: nprocure@anvfo.net Mobile: 93270 84190, 9925117079
3.3	Bidders who already have a valid Digital certificate need not procure a new Digital certificate.
4.0	Online Submission of Price-Bid.
4.1	Bidders can prepared and edit their offers number of times before tender submission date and time. After tender submission date and time, bidder cannot edit their submitted offer in any case. No written or online request in this regard shall be granted.
4.2	Tenderer shall submit their offer i.e. Price bid in electronic format on above mentioned web site and date shown above after Digitally Signing the same.
4.3	Offers submitted without digitally signature will not be accepted.
4.4	Offers in physical form will not be accepted in any case.
5.0	Submission of Tender Fees, Bid Security and other Documents:
5.1	Tender Fee of work by Demand Draft in favor of " Registrar, Bhakta Kavi Narsinh Mehta University - Junagadh ", payable at Junagadh from any Nationalized/Scheduled Bank. Demand Draft issued after the last date of submission of Bids will not be considered or accepted.
5.2	Bid Security i.e. EMD: of work In the form of DD in favor " Registrar, Bhakta Kavi Narsinh Mehta University - Junagadh ", from any Nationalized/ Scheduled Bank. DD issued before issuing of tender notice or after the last date of submission of tender will not be considered as valid or accepted in any case.
5.3	Documents required FOR ELIGIBILITY OF TENDER to be submitted electronically online: 1. Tender Fee, Earnest money deposit(EMD) in demand draft (DD) in favor of "Registrar, Bhakta Kavi Narsinh Mehta University - Junagadh", payable at Junagadh from any Nationalized/Scheduled Bank.



ભક્તકવિ નરસિંહ મહેતા યુનિવર્સિટી, જૂનાગઢ

	2. Experience as a prime contractor of having successfully completed minimum one similar work of Rs. 45 Lacs government, semi-government or local self-government which are completed during last 3 years. (Form-3A should be submitted issued by the owner). 3. Photo copy of PAN card. 4. Photo Copy of GST Registration No. 5. Partnership Deed if not Proprietor 6. Binding Latter (બાહેંધરી પત્રક) on Rs. 300/- Stamp notarized. 7. PF no/ if not applicable PF act submit on affidavit 300/- stamp paper notarized. 8. Average annual financial turnover from 50% of the estimated cost for related activities in the last 3 financial years. (CA Certified) 9. Valid Bank solvency certificate for the current calendar year. 10. Steel Support Structure Dome Certificate by Structure Engineer
5.4	Bidder has to submit the valid documents as stated in 5.1, 5.2, 5.3 & 5.4 above and no other condition in any form shall be considered at all, at the time of evaluation of the tender. The bidder shall have to submit unconditional offer without differing from any of the tender condition. If any document is not submitted by scanning in preliminary stage itself as per 5.1, 5.2, 5.3 & 5.4 such Tender shall be considered as non- responsive.
6.0	Opening of Tender:
6.1	Opening of bid documents will be held on Date & time shown as under: Tender will be open in the Office of the Bhakta Kavi Narsinh Mehta University, Junagadh
6.2	Intending bidders or their representative who wish to remain present in Division office at the time of tender opening can do so.
6.3	After successful completion of technical bid of only those bidders would be opened online who are found to be substantially responsive.
7.0	Contacting Officer:
7.1	Further details / clarification of any required will be available from <u>University Civil Engineer, Estate department, BKNMU, Junagadh</u>
7.2	In case bidder needs any clarification / assistance or if training required for participating in online tender, they can contact at following office. (n) Code solutions A division of GNFC 301, GNFC Info tower, Bodakdev, Ahmedabad - 380 054 (India) Tel: +91 26857816/17/18 Fax: +91 79 26857321 E-mail: nprocure@anvfo.net Mobile: 93270 84190, 9925117079
8.0	SPECIFIC INSTRUCTION TO APPLICANTS:
8.1	The principal items covered in the contract as above
8.2	The Contract will be price rate contract:
8.3	The language for submission of pre-qualification documents along with the tender documents shall be ENGLISH. If information is provided in another language, it shall be accompanied by a translation of its pertinent parts into ENGLISH. This translation will govern and be used for interpreting the information.
8.4	The cost incurred by the contractor for this offer for clarification or attending discussion, conferences or site visits will not be reimbursed by the Employer or



ભક્તકવિ નરસિંહ મહેતા યુનિવર્સિટી, જૂનાગઢ

	Engineer-in-Charge.
8.5	Submission of All EILIGIBLE documents duly certified along with application & tender fee & E.M.D. shall have to furnish to University Civil Engineer, Estate department, BKNMU, Junagadh by R.P.A.D./SPEED POST on or before 27/01/2026 during office hours.
9.0	General Instruction:
9.1	The fees for on line tender document will not be refunded under any circumstances.
9.2	EMD in the form specified in tender document only shall be accepted.
9.3	Tenders without Tender document fees, Earnest Money Deposit (EMD) and which do not fulfill all or any of the condition or submitted incomplete in any respect will be rejected.
9.4	Conditional tender shall not be accepted.
9.5	Validity of tender shall be 180 Days from the date of online opening of price bid.
9.6	The tender notice shall from a part of tender document.
9.7	The tenderers are advised to read carefully the "Instruction for Tenderer" and "Eligibility Criteria" contained in the tender documents.
9.8	The Internet site address for E-Tender is https://tender.nprocure.com
9.9	The University reserves the rights to reject any or all tenders without assigning and reason thereof BKNMU, Junagadh

MEMORENDEM OF WORK IN BRIFF

1.	Name of work	Providing Mandap Stage and Other Necessary Facilities for 2 Year Rate Contract on Various Govt. Functions at Bhakta Kavi Narsinh Mehta University, Junagadh. Mehta University, Junagadh.(2 nd Attempt)
2.	EMD	Rs. 1,35,000/-
3.	Validity Period of Tender Offered	(180) days from last actual date of up-loading of Bid
4.	Security Deposit	5 % of contract value (D.D.)
5.	Tender Fee	Rs. 2,500/-
6.	Time allowed for completion of the work from the date of written order to commence	2 Year
7.	Workers Welfare Cess	1% of the value of work done shall be deducted from all the bills payable to the contractor.
8.	TDS	Shall be deducted from the bills payable to the contractor as per prevailing Government rules.



ભક્તકવિ નરસિંહ મહેતા યુનિવર્સિટી, જૂનાગઢ

TENDER DECLARATION FORM

To,
The Registrar,
Bhakta Kavi Narsinh Mehta University,
Junagadh.

NAME OF WORK: - Providing VVIP/VIP Mandap On Hire Basis For Govt. Functions To Be Held Under Jurisdiction of Bhakta Kavi Narsinh Mehta University, Junagadh (2nd Attempt)

Respected Sir,

I/We the undersigned have carefully gone through and clearly understood the Tender documents comprising Notice Inviting Tender, Scope of work, Instructions to Tenderer, furnished by Bhakta Kavi Narsinh Mehta University, Junagadh.

I/We hereby offer to execute and complete the work within the time specified, all in accordance with the instructions in writing referred to in the said documents and with such materials as are provided for at the respective rates which I/We have quoted, or at such other rates as may be fixed under the provisions of these conditions.

In the event of this tender being accepted, I/We agree to enter into an agreement as and when required and execute the contract, according to your Form of Agreement or in default where of I/We find myself / ourselves to forfeit the Earnest Money Deposit.

I/We understand that if I/We shall enter in agreement within ten days from the date of receipt of letter of Acceptance, you will forfeit the Earnest Money paid by me/us and take necessary action as deemed fit.

I/We have enclosed a Draft as an "Earnest Money Deposit" for the sum of **Rs.1,35,000.00 Rupees One Lacs Thrity Five Thousand Only** the full value of which is to the absolutely forfeited to the employer should I/We fail to commence the works specified. Otherwise the said sum shall be retained, by the Employer, as on account of such Security Deposit as provided for in the aforesaid documents.

I/We agree not to employ sub-contractors other than those that may be approved in accordance with conditions in the aforesaid documents.

I/We understand that you are not bound to accept the lowest of any tender, which you may receive.

I/We understand that all the pages of the Tender documents are to be signed by me/us.

I/We shall refer all disputes arising out of or relating to the agreement to the arbitration in accordance with conditions of contract.

I/We agree to pay the Income Tax, Sales Tax (Central and State), work contract Tax Excise, GST etc. and other taxes prevailing from time to time on such items the same are livable and the rates quoted by me/us are inclusive of all Taxes.

Sr.N	Days	Percentage
1	FIRST DAY	100%
2	SECOND DAY	20% of first day
3	THIRD DAY & CONTINUE	10% of first day

Signature of Contractor

ભક્તકવિ નરસિંહ મહેતા યુનિવર્સિટી, જૂનાગઢ

ટેન્ડરની શરતો –

1.	આ કામની ટેન્ડર ફી રૂ. ૨૫૦૦/- રજીસ્ટ્રાર, ભક્તકવિ નરસિંહ મહેતા યુનિવર્સિટી, જુનાગઢના નામનો ડીમાન્ડ ડ્રાફ્ટ (શિઝ્યુલ્ડ/રાષ્ટ્રીય બેન્કનું) ટેન્ડર ડોક્યુમેન્ટ સાથે સામેલ કરવાની રહેશે.
2.	આ કામ અંગે પૂર્વપાત્રતા (પ્રિ-ક્વોલીફિકેશન) માં સફળ થયેલ પાર્ટી/એજન્સીના જ ભાવ પત્રકો (પ્રાઈસ બીડ) ખોલવામાં આવશે.
3.	કરારની સમય મર્યાદા કરાર કર્યા તારીખથી ૨૪ માસની રહેશે.
4.	ભક્તકવિ નરસિંહ મહેતા યુનિવર્સિટી, જુનાગઢ ખાતે સુચવેલ જગ્યાએ તમામ કામગીરી બેઠક વ્યવસ્થા વિગેરે યુનિવર્સિટી દ્વારા રિઈસલ માટેનો જે દિવસ નક્કી કરવામાં આવે તેના આગલા અથવા પ્રોગ્રામના એક દિવસ પહેલાના દિવસે (બે માંથી જે વહેલું હોય તે) સંપૂર્ણકામ પૂર્ણ કરી તેનો કબ્જો લગત વિભાગને સોંપી આપવાનો રહેશે. તેમજ દરેક આઈટમની સાફ-સફાઈ, ફેરવણી અને જાળવણી, પ્રોગ્રામ પુરો થતાં સુધી વિભાગને સંતોષકારક લાગે તે રીતે કરવાની રહેશે.
5.	દરેક આઈટમની કામગીરી તમને જાણ કરવામાં આવે કે તુર્તજ પૂર્ણ પાછો સંતોષકારક થાય તે રીતે કરવાની રહેશે. તમામ કામગીરી યુનિવર્સિટી દ્વારા અધિકૃત કરેલ અધિકારીશ્રીઓની સુચના મુજબ કરી આપવાનું રહેશે.
6.	જરૂરિયાત મુજબનો મંડપ સ્વચ્છ, સુઘડ તથા વી.વી.આઈ.પી. પ્રોગ્રામને અનુલક્ષીને સારી જાતના કાપડ ઉપર તાડપત્રીવાળો તથા ફર્નિચર તેમજ અન્ય આવશ્યક વસ્તુઓ અધિકૃત કરેલ અધિકારીશ્રીઓની સુચના મુજબની તથા તેઓ જે પ્રમાણે સુચના આપે તે સ્થળે, સમય મર્યાદામાં તાત્કાલીક બાંધી આપવાનો રહેશે. મંડપ તથા ફર્નિચર લાવવા લઈ જવાનો સઘનો ખર્ચ ભાવ ભરનારે ભોગવવાનો રહેશે. સમય મર્યાદામાં કામ પૂર્ણ ન થતાં અન્ય ઈજારદાર પાસે કોઈપણ જાતની લેખિત જાણ કર્યા સિવાય મુળ ઈજારદારના ખર્ચે અને જોખમે કામ કરાવી લેવામાં આવશે. મંડપ બાંધકામની કામગીરી દરમિયાન માલસામાનને કોઈપણ જાતનું નુકશાન થશે તેની સઘળી જવાબદારી પાર્ટી/એજન્સીની પોતાની રહેશે.
7.	જે ઈજારદારના ટેન્ડર મંજૂર કરવામાં આવશે તેમણે રૂ. ૨,૨૫,૦૦૦/- જામીન અનામત (સિક્યુરિટી ડીપોઝીટ) તરીકેનો ડી.ડી. રજીસ્ટ્રાર, ભક્તકવિ નરસિંહ મહેતા યુનિવર્સિટી, જુનાગઢના નામે રજુ કરવાનો રહેશે અને તે રકમ ટેન્ડરની મુદત પુરી થયેથી કામગીરી સંતોષકારક કરી હશે તો જ પરત કરવામાં આવશે. વધુમાં સિક્યુરિટી ડીપોઝીટ સાથે રાજ્યસરકારશ્રીના નિયમાનુસારની સ્ટેમ ડ્યુટી ઈજારદારે ભરવાની રહેશે.
8.	કોઈપણ જાતના શરતી ટેન્ડર માન્ય રાખવામાં આવશે નહિ.
9.	સરકારશ્રીના આ અંગેના વખતો વખતના નિયમો પાર્ટી/એજન્સીને બંધનકર્તા રહેશે.
10.	કોઈપણ એક કે બધા ટેન્ડર કોઈપણ કારણ દર્શાવ્યા સિવાય મંજૂર/નામંજૂર કરવાના હકક ભક્તકવિ નરસિંહ મહેતા યુનિવર્સિટી, જુનાગઢને અબાધિત રહેશે.
11.	વી.વી.આઈ.પી. કાર્યક્રમો દરેક સ્થળે પોતાના ઓછોમાં ઓછા બે થી વધારે અધિકૃત પ્રતિનિધિ નિયુક્ત કરી તેની જાણ લેખિતમાં મોબાઈલ નંબર સાથે ભક્તકવિ નરસિંહ મહેતા યુનિવર્સિટી, જુનાગઢના અધિકૃત કરેલ અધિકારીને જાણ કરવાની રહેશે.
12.	મંડપ વિગેરેનું કાપડ, તાડપત્રી તથા ફર્નિચર વિગેરેની આઈટમો યુનિવર્સિટી દ્વારા અધિકૃત કરેલ અધિકારીશ્રી જે પસંદ કરે તે જ જરૂરી પ્રમાણના જથ્થામાં પુરુ પાડવાનું રહેશે. તે સિવાયની જરૂરિયાત વગરની આઈટમો રદ કરવામાં આવશે. અને તેનું ચુકવણું કરવામાં આવશે નહીં.
13.	ટેન્ડરમાં દર્શાવેલ આઈટમોની સામે પ્રોગ્રામને અનુલક્ષીને કામગીરી કરવાની રહેશે. કોઈ પાર્ટી/એજન્સી દ્વારા આ રીતે કામ ન મળવા બાબતે કોઈ કહેવાતા નફા-નુકશાન વગેરે અંગે કોઈપણ પ્રકારનો હકક, દાવો કરી શકાશે નહીં. તાકીદના કિસ્સામાં જેના ભાવો મંજૂર થાય તે સિવાયની અન્ય એજન્સી પાસે પણ મંજૂર થયેલા ટેન્ડરના ભાવે આપું કામ કરાવવા માટે વિભાગ સ્વતંત્ર રીતે નિર્ણય લઈ કામ કરાવી શકે છે. તથા આ બાબતે કોઈ દાદ, ફરીયાદ કે તકરાર ચલાવી લેવાશે નહીં.
14.	સરકારી ઉત્સવ રાજ્યની પ્રતિષ્ઠાના પ્રતિબિંબ સમાન હોઈ મંડપ, ફર્નિચર, કોકરી, કટલેરી વિગેરે બધી જ આઈટમો સારી જાતની ઉચ્ચ ગુણવત્તાવાળી પૂરી પડવાની રહેશે તથા કાર્યક્રમના સ્થળ પર પહોંચાડવાની રહેશે. તમામ વસ્તુઓ સારી રીતે સફાઈ થયેલી હોવી જોઈએ. તેમાં કોઈપણ જાતની છુટછાટ આપવામાં આવશે નહીં. આ બાબત ખાસ ધ્યાને રાખવી જરૂરી છે.

15.	ગાદલાં, તકીયા, ગાદી, ચાદરો વિગેરે દાગ રહિત સ્વચ્છ, ઘોલાઈ કરી ઈસ્ત્રી કરેલા પુરા પાડવાના રહેશે.
16.	મંડપ વિગેરે બાંધનાર પાર્ટી/એજન્સીના અધિકૃત માણસો, મજુરોનું વર્તન સભ્યતાભર્યું હોવું ખુબ જ આવશ્યક છે. અસભ્ય વર્તન માટે કચેરીના વડાને લેખિતમાં ફરીયાદ થશે તો ટેન્ડર અધવચ્ચેથી રદ કરીને ટેન્ડર સાથે ભરેલ ડીપોઝીટ જમ કરી યુનિવર્સિટીમાં જમા કરાવવામાં આવશે. અને બાકીનું કામ અન્ય પાર્ટી/એજન્સી પાસેથી કરાવી લેવામાં આવશે. તેમજ જરૂરીયાત મુજબનું કામ આપેલ સમય મર્યાદામાં કરવામાં આવશે નહીં તો ટેન્ડર સાથે ભરેલ ડીપોઝીટ જમ કરવામાં આવશે.
17.	કામના જથ્થા, ગુણવત્તા અને જરૂરિયાત અંગે કોઈપણ તકરાર કે ગુંચવણ ઉભી થશે યુનિવર્સિટી સિવિલ એન્જીનીયરશ્રી, બાંધકામ વિભાગનો નિર્ણય આખરી અને અંતિમ રહેશે જે હેકેદારને બંધન કરતા રહેશે, નિયત સમય મર્યાદામાં પૂર્ણ નહિ થયેલ કે શરતો અનુસાર અને સાઈટ ઈન્ચાર્જની સુચના અન્વયે અધૂરાશવાળી કામગીરી માટે સક્ષમ અધિકારી દંડની જે રકમ નિયત કરે તે બીલમાંથી કપટ કરવામાં આવશે તેમજ અન્ય હેકેદાર પાસેથી આ કામના હેકેદારના હિસાબે અને જોખમે આવી અધુરાશ પૂર્ણ કરવામાં આવશે અને તેના ચુકવણા અંગે કોઈ બાબતે તકરાર કરી શકાશે નહીં.
18.	કરાયેલ કામનું ચુકવણું યુનિવર્સિટી દ્વારા કરવામાં આવશે, ચુકવણાં માટે એજન્સીની કોઈ પણ જાતની તકરાર તથા નાણાં વ્યાજ સાથે ચુકવણી રજુઆત ધ્યાનમાં લેવામાં આવશે નહીં તેમજ ચુકવણું મોડું થવા બાબતે કોઈ દાવો કરી શકશે નહીં.
19.	થયેલ કરારનો કોઈપણ સમયે કોઈપણ કારણ આપ્યા વગર ફેક્સ, ટેલીફોન અને મેસેજથી નોટીસની જાણ કર્યાના 3-કલાકમાં અંત લાવવાનો યુનિવર્સિટી સત્તામંડળનો હકક અબાધિત રહેશે.
20.	વી.વી.આઈ.પી. કાર્યક્રમોનાં મંડપ તથા સ્ટેજની કામગીરી માટે યુનિવર્સિટીની સુચના મુજબ તમામ કામગીરી કરવાની રહેશે. અને તેમાં કોઈ ફેરફાર કરવાનો થાય તો તેનો ફેરવણી કે તુટકુટનો ચાર્જ અલગથી આપવાનો રહેશે નહીં.
21.	વી.વી.આઈ.પી. કાર્યક્રમો માટે યુનિવર્સિટીની સુચના મુજબ જરૂર જણાયે સ્ટેજ ઉપર ડબલ તાડપત્રીવાળા મંડપ / ડોમ / રસોડા વિગેરેની કામગીરી કરી આપવાની રહેશે.
22.	સ્થળ પરના કાર્યક્રમો માટે નિયત કરાયેલ સ્ટ્રક્ચર ડોમ, ટીન શેડ તેમજ મંડપ બાંધવાના રહેશે. આ સ્ટ્રક્ચરની મજબુતાઈ અંગે એજન્સી દ્વારા જરૂરી કરવાનું રહેશે. તથા તેની સલામતીની સંપૂર્ણ જવાબદારી જે તે પાર્ટી/એજન્સીની રહેશે. આ અંગેનો કોઈ વધારાનો ચાર્જ ચુકવવામાં આવશે નહીં.
23.	પાર્ટી/એજન્સીએ વર્તમાનમાં સરકારશ્રી દ્વારા નક્કી કરેલ બધા ટેક્સ એટલે કે જીએસટી, આવકવેરા તથા લેબર સેસ અને અન્ય લાગુ પડતા ટેક્સ સહિત ભાવ ભરવાના રહેશે. કોઈપણ પ્રકારના ટેક્સનું વિભાગ દ્વારા અલગથી ચુકવણું કરવામાં આવશે નહીં તથા કરેલ કામના ચુકવણાંમાંથી સરકારશ્રી દ્વારા નિયત કરવામાં આવેલ વેરાની કપાત કરવામાં આવશે.
24.	આંકડા અને શબ્દમાં ભરેલ ભાવોમાં તફાવત જણાશે તો શબ્દોમાં ભરેલા ભાવો જ ગણતરીમાં લેવામાં આવશે.
25.	ટેન્ડર સિવાયની વધારાની આઈટમની કામગીરી યુનિવર્સિટીની સુચના મુજબ કરવાની રહેશે. અને તેનું ચુકવણું સરકારશ્રીનાં ધારા ધોરણ મુજબ પ્રવર્તમાન બજાર ભાવો મુજબ સક્ષમ કક્ષાએથી મંજૂરી મળ્યે ચુકવણું કરવામાં આવશે. ટેન્ડર આઈટમના વધારાના જથ્થાનું કામ યુનિવર્સિટી દ્વારા મંજૂર થયેલા ટેન્ડરના ભાવોથી અન્ય પાર્ટી/એજન્સી પાસેથી કરાવવા સ્વતંત્ર રહેશે જે માટે ઈજારદાર કોઈ વાંધો લઈ શકશે નહીં.
26.	વી.વી.આઈ.પી. પ્રોગ્રામની વિગતો કાયદાકીય જોગવાઈ અનુસાર સંપૂર્ણ પણે ગોપનીય અને સુરક્ષિત રાખવાની રહેશે.
27.	આ કામગીરી દરમિયાન પુરા પાડવામાં આવેલ માલ-સામાનની ચોરી, પોતાના સમીયાણા, મંડપ માં કાંઈ તોડફોડ, નુકશાન કે આકસ્મિક આગ (જેવી કે શોટ સર્કિટ), કુદરતી આફત, અકસ્માતથી સરકારી / ખાનગી ઇમારત ને કોઈ પણ નુકશાન થાય તો તે અંગેની સઘળી જવાબદારી કામ રાખનાર પાર્ટી/એજન્સીની રહેશે અને આ અંગે વિમો વિગેરે પાર્ટી પોતાના ખર્ચે રહેશે. આ માટે કામ આપનાર યુનિવર્સિટીની કોઈ જવાબદારી રહેશે નહીં.
28.	જરૂરી અગ્રી શામક સાધન સામગ્રીની વ્યવસ્થા પાર્ટી/એજન્સીએ કરવાની રહેશે તથા તે માટે કોઈ અલગથી ચુકવણું કરવામાં આવશે નહીં.

29.	આ કાર્યક્રમ સિવાય તેને લગતા યુનિવર્સિટીના અન્ય કાર્યક્રમો અન્ય જગ્યાએ કરવાના થશે તો પાર્ટી/એજન્સીએ આજ ભાવે કામગીરી કરી આપવાની રહેશે.
30.	આ કામગીરી માટે પાર્ટીએ લેબર (રેગ્યુલેશન એન્ડ એબોલેશન) એક્ટ, ૧૯૭૦ તથા તે હેઠળ ૧૯૭૨ના ગુજરાત નિયમોની જોગવાઈઓ તથા કામદાર વળતર અધિનિયમ-૧૯૨૩ તથા તે હેઠળના નિયમોની જોગવાઈ અનુસાર ઠેકેદારે રોકેલ મજુરોના કાયદેસરના હિતોની રક્ષા કરવાની તેમજ પ્રસ્તુત કાયદા અને નિયમો હેઠળ કરાયેલ સુવિધા / સગવડો ઉપલબ્ધ કરાવવાનો પ્રાથમિક અને વૈધાનિક જવાબદારી મજુર કામે રાખનાર જે તે ઈજારદારશ્રીની રહેશે. અને આ કામગીરી દરમિયાન કામદારોને થતાં અકસ્માતની શારીરિક ઈજા થાય તો તે અંગેની સઘળી જવાબદારી વળતર સહિતની ઈજારદારશ્રીની રહેશે. સદર કામગીરીમાં બાળ મજુરો રાખી શકાશે નહીં. આ અંગે યુનિવર્સિટીની કોઈપણ પ્રકારની જવાબદારી રહેશે નહીં.
31.	આ કામ માટે ઈજારદારે તેમની પેઢીનું નામનું જે તે સ્થળનું શોપ એસ્ટાબ્લીશમેન્ટ સર્ટીફિકેટ અથવા તો આ જાતની કામગીરી/ધંધાનું રજીસ્ટ્રેશનની અમલમાં હોય તેવું તાજેતરના પ્રમાણપત્રની પ્રમાણિત નકલ ભાવ પત્રક સાથે સામેલ રાખવાની રહેશે.
32.	ટેન્ડર ભરનાર આસામી દ્વારા ખોટી માહિતી આપવાનું કે ખોટા પ્રમાણપત્ર, દસ્તાવેજ રજુ કર્યાનું ધ્યાને આવશે તો તે ઈજારદાર જે તે કામ માટે ગેરલાયક ઠરશે અને તેની બાનાની રકમ જપ્ત કરવામાં આવશે અને તેની સામે કાયદાકીય કાર્યવાહી કરવામાં આવશે.
33.	તમામ ભાવો સમગ્ર કાર્યક્રમની કમ્પ્લીટ આઈટમો માટેનાં ગણવામાં આવશે.
34.	તમામ પ્રોગ્રામોમાં સક્ષમ અધિકારીશ્રીની સુચના અનુસાર બેઠક વ્યવસ્થા માટે ખુરશીઓ, સોફા વિગેરે ઠેકેદારશ્રી દ્વારા ગોઠવી આપવાનાં રહેશે તથા રોજ બરોજ પ્રોગ્રામ પૂર્ણ થવા સુધી સફાઈ કરવાની રહેશે.
35.	પ્રોગ્રામને અનુરૂપ વપરાશમાં લેવાની થતી એટ્રો નેટ ફ્લોરીંગ તથા કારપેટ નવી જ છેડા ઓટેલી વાપરવાની રહેશે અને તે પ્રથમ યુનિવર્સિટી પાસેથી મંજુર કરાવવાની રહેશે અને ગ્રાઉન્ડની સફાઈ કર્યા બાદ જ પાથરવાની રહેશે.
36.	ટેન્ડર સિવાયની સુચવવામાં આવેલ કોઈપણ નવી અથવા વધારાની કામગીરી પૂર્ણ કરવામાં ચુક થશે તો યુનિવર્સિટી દ્વારા સૂચવવામાં આવે તે રકમની પેનલ્ટી બીલમાંથી કપાત કરવામાં આવશે.
37.	મંડપને લગત કામગીરી માટે, ખાડા કરવા માટે બ્રેકરની જરૂરીયાત ઉભી થાય તો તેનું અલગથી ચુકવણું કરવામાં આવશે નહીં.
38.	ડોમનાં પીલરમાં બેઈજ પ્લેટ યોગ્ય રીતે એન્કર કરવાની રહેશે અને જમીન પોચી લાગે અથવા જરૂરી લાગે તો સુચના મુજબનું કોર્કીટ કરવાનું રહેશે. જેનું અલગથી ચુકવણું કરવામાં આવશે નહીં.
39.	વપરાશમાં લેવાનું થતું કાપડ પ્લેઈન અથવા કલરફુલ વિગેરે નવું જ યુનિવર્સિટીની સુચના મુજબ મંજુર કરાવ્યા બાદ વાપરવાનું રહેશે.
40.	દરેક કાર્યક્રમના સ્થળ પરના ચોમાસા દરમિયાન પાણીના નિકાલ માટે જરૂરીયાત મુજબનાં હેવી કેપેસિટીનાં સ્ટેન્ડ ટુ સક્શન પમ્પો આશરે ૫ નંગ પૂરતી લંબાઈ તથા ડાયામીટરનાં સારી જાતનાં પાઈપ / પીવીસી / ફ્લેક્સીબલ સાથે કાર્યક્રમનાં દરેક સ્થળો પર ઠેકેદારશ્રી દ્વારા ચાલુ હાલતમાં તૈયાર રાખવાનાં રહેશે. આ અંગે અલગથી ચુકવણું કરવામાં આવશે નહીં.
41.	રૂના ગાદલાઓ સારી કવોલીટીનાં તેમજ કોઈપણ જગ્યાએથી ફાટેલ કે મેલા ન હોવા જોઈએ. ઓછાડ સ્વરછ, સુઘડ તથા ઘોચેલા હોવા જોઈએ. ગાદલાઓ ઠેકેદારશ્રી તરફથી સ્થળ પર લઈ આવી વ્યવસ્થિત રીતે સુચના આપ્યા મુજબ પાથરી તેના પર ઓછાડ પાથરી આપવાના તથા કાર્યક્રમ પૂરો થયે ઉપાડી લેવાના રહેશે.
42.	દરેક કાર્યક્રમના સ્થળ ઉપર ઠેકેદારશ્રી દ્વારા એક સુપરવાઈઝર નિયુક્ત કરવાનો રહેશે. જેમાં રાઉન્ડ ઘી કલોક સુપરવાઈઝરે આયોજિત સ્થળ પર હાજર રહેવાનું રહેશે. આપવામાં આવેલ સુચનાનો અમલ બે કલાક સુધીમાં કરવાનો રહેશે.
43.	યુનિવર્સિટી દ્વારા નક્કી કરવામાં આવેલ કાર્યક્રમના સ્થળ પર દવાનો છંટકાવ એજન્સી દ્વારા કરવાનો રહેશે.
44.	વી.વી.આઈ.પી. કાર્યક્રમોનાં સ્થળે તૈયાર કરવાના થતાં ડોમ તેમજ ટીનશેડનાં છાપરાના પાણીનાં નિકાલ માટે જી.સી.આઈ. શીટમાંથી બનાવેલ અથવા પી.વી.સી. ફાઈબરની હાફરાઉન્ડ ગટર તૈયાર કરી ફીટ કરી તેમાં સુચના આપવામાં આવે તે ડાયામીટરનાં હોલ કરી તેમાં એર ટાઈટ સુચના મુજબની ડાયામીટરનાં સુચના પ્રમાણેનાં અંતરે ઉભા પી.વી.સી. પાઈપ ફીટ કરી તેના નીચેના છેડે આડો સુચના મુજબનો પી.વી.સી. પાઈપ સમગ્ર શેડની લંબાઈનો દરેક ઉભા તથા આડા પાઈપમાંનાં ટી-જોઈન્ટ સોલ્યુશનથી એસ્ટાઈટ ચોંટાડી પાઈપોને ફીટ કરી

ભક્તકવિ નરસિંહ મહેતા યુનિવર્સિટી, જૂનાગઢ

	સમીચાણાનો પાણીનો નિકાલ ઠેકેદારશ્રી દ્વારા કરવાનો રહેશે. આ અંગેનું કોઈપણ જાતનું અલગ ચુકવણું કરવામાં આવશે નહીં.
45.	સમારભનું દર્શાવેલ સ્થળ સુચિત સ્થળ છે. સંજોગોવસાત તેમાં ફેરફાર થશે તો બદલાવેલા સ્થળ પર મંજૂર થયેલ ભાવે કામગીરી કરવાની રહેશે.
46.	કાર્યક્રમના સ્થળે યુનિવર્સિટીના કાર્યક્રમ ઈન્ચાર્જ/અધિકારીઓ/સ્ટાફ માટે ઓફિસ કામ શરૂ કરતા પહેલા ત્યાં તૈયાર કરવાની રહેશે. જેમાં સુચના મુજબ ટેબલ / ખુરશી / સોફા / ટીપોઈ / પેન્ડ્રી / ગ્લાસ/ ટ્રે/કપ/રકાબી/ પીવાના પાણીની વ્યવસ્થા વગેરેની સુચના મુજબ ગોઠવણી કરવાની રહેશે. જેનું અલગથી ચુકવણું કરવામાં આવશે નહીં.
47.	યુનિવર્સિટી દ્વારા પુરા પાડવામાં આવેલ ફ્લેક્સ/બેનર પ્રોગ્રામ સ્થળે, ડાયસ ઉપર કે શહેરની અન્ય કોઈ જગ્યાએ યુનિવર્સિટીની સુચના મુજબ લગાવી આપવાના રહેશે અને પ્રોગ્રામ પૂર્ણ થયે આ બેનર વ્યવસ્થિત રીતે કાઢીને યુનિવર્સિટીને પરત કરવાના રહેશે.
48.	ટેન્ડરની તમામ આઈટમના કમ્પેટેટીવ સ્ટેટમેન્ટ બનાવતાં સૌથી નીચા ભાવો ધ્યાને લઈ, તેમાં જે ઈજારદારશ્રીની સૌથી વધારે આઈટમોના ભાવો નીચા હશે તેઓને વાટા-ઘાટો પ્રાયોરીટી આપવામાં આવશે, અને તે પ્રક્રિયાથી એજન્સી નક્કી કરવામાં આવશે.
49.	પ્રોગ્રામ પૂર્ણ થયેથી યુનિવર્સિટીના ઈજનેરશ્રીની હાજરીમાં થયેલ કામના માપો લેવાના રહેશે, તેમજ અરસ-પરસ સંમતિરૂપે સહી-સિક્કા કરી આપવાના રહેશે, અન્યથા યુનિવર્સિટી તરફથી લીધેલ માપો માન્ય રાખવામાં આવશે તેમજ તે અંગે કોઈજ જાતની દાદ કે ફરીયાદ ધ્યાને લેવામાં આવશે નહીં.
50.	ભક્તકવિ નરસિંહ મહેતા યુનિવર્સિટી, જુનાગઢના વિવિધ કાર્યક્રમોની કામગીરી જો ઠેકેદાર દ્વારા સંતોષકારક રીતે કરવામાં આવેલ હશે તો આ ટેન્ડરની સમય મર્યાદા વધુ ૧ વર્ષ સુધી વધારવી કે નહિ તેનો નિર્ણય યુનિવર્સિટીના સત્તામંડળની રહેશે. જો ટેન્ડરની સમયમર્યાદા વધારવામાં આવે તો મૂળ ટેન્ડરમાં ભરેલ ભાવો જ માન્ય રહેશે, ભાવોમાં કોઈ વધારો આપવામાં આવશે નહીં.
51.	આ કામગીરીના ટેન્ડર મંજૂર/નામંજૂર કરવાની સત્તા ભક્તકવિ નરસિંહ મહેતા યુનિવર્સિટી, જુનાગઢની અબાધિત રહેશે.
52.	તમામ આઈટમોના ભાવ સમારોહના આગલા દિવસના તેમજ સમારોહના દિવસ માટે ભરેલ ભાવના ૧૦૦% લેખે ગણવાના રહેશે અને અને જો સમારોહ બે દિવસ ચાલે તો બીજા દિવસના ભરેલ ભાવના ૨૦% લેખે ગણવામાં અને ચુકવવામાં આવશે અને જો સમારોહ બે દિવસ કરતા વધુ ચાલે તો ત્રીજા દિવસના અને બાકીના તમામ દિવસો માટે મંજૂર થયેલ ભાવોના ૧૦% લેખે ગણવામાં અને ચુકવવામાં આવશે
53.	ટેન્ડર ભરનાર વ્યક્તિ/કંપની/પેઢીની ઓફિસ ગુજરાત રાજ્યમાં હોવી જ જોઈએ અને સંચાલનકર્તાનું નામ તથા સરનામાની વિગતો અચૂક પૂરી પાડવાની રહેશે.
54.	જે પાર્ટીના ભાવ મંજૂર થાય તે પાર્ટીએ રૂ.૩૦૦૦ના સ્ટેપ પર કરારખત કરાવવાનો રહેશે.
55.	આ કામના હુકમ/કરાર બાબતે કોઈપણ વિવાદ અને કાનુની ગુંચ ઉદભવે તો તે અંગેની બાબત જુનાગઢ જિલ્લા કાર્યક્ષેત્ર હેઠળ નિકાલ કરી શકાશે.

મંડપ અને સ્ટેજ સર્વિસના બીડની ઉપરોક્ત તમામ શરતો અને સુચનાઓ અમોએ બરોબર પુરેપુરી વાચી છે. અમોને દરેક પ્રકારે સંપૂર્ણ કબુલ મંજૂર તથા બંધનકર્તા છે. જે બદલ આથી નીચે સહી કરી ટેન્ડર રજૂ કરેલ છે.

તારીખ :

ટેન્ડર ભરનાર પાર્ટીનું નામ સહી તથા સિક્કો



ભક્તકવિ નરસિંહ મહેતા યુનિવર્સિટી, જૂનાગઢ

**Inviting e-Tendering Notice for Providing Mandap Stage and
Other Necessary Facilities for Various Functions at Bhakta Kavi
Narsinh Mehta University, Junagadh. (2nd Attempt)
(Item Rate on Annual Base)**

**Financial Bid For Online Only
Schedule - B**

ESTATE SECTION				
Name of Work : Providing VVIP/VIP Mandap On Hire Basis For Govt. Functions To Be Held Under BKNM University Campus , Junagadh (2nd Attempt)				
SCHEDULE -B				
Item	Item of Work	Quantity	Unit	Rate
1	Providing & erecting German Alluminium Fabricated Structural Dome having width up to 150 feet & minimum central apex hight of 36 feet from G.I. roof covered with Blue and Grey SRF Fabric (Waterproof and Fire Resistant) using snow white or colourful cloth ceiling has tube provided below the cover including colourful "Zalar" on each ring and tricolour or colourful facia on the front of the dome including every vertical pillar of dome should be supported with bottom plate support arrange as per structural stability as per design structural engineer with efficient rain water drainage system and dome side as directed by engineer in charge, side height 20' so as to accomodate stage light truss inside including submission of the structural stability certificate for dome from Govt. approved structural engineer prior to function day to Engineer in charge. as directed by engineer in charge.	1.00	Sqm	
2	Providing Mandap with approved Coloured neat-clean Cloth for sealing Patta, Zool, with Mandap from Cross Bracing by using 2" to 3" thick long Balles / Bamboo.	1.00	Smt.	
3	Providing Mandap with approved Coloured neat-clean Cloth for sealing Patta, Zool, with water proof Mandap from Cross Bracing by using 2" to 3" thick long Balles / Bamboo.	1.00	Smt.	
4	Pipe Mandap with steel structure Single Height mandap upto 12 ft height (including zool, vali, patta neat clean) including necessary excavation fitting, up to 16' height etc. comp. as per instruction.	1.00	Smt.	
5	Pipe Mandap with steel structure Single Height water proof mandap 12 ft (Incl. zool, vali patta) neat-clean including necessary excavation fitting, etc. complete as per instruction.	1.00	Smt.	
6	Pipe Mandap with steel structure-Double Height (including Zool, Vali Patta neat-clean) Height above 3.00 Mtr. To 6.00 Mtr.	1.00	Smt.	
7	Pipe Mandap with steel structure-Double Height water proof mandap (including Zool, Vali Patta). The cloth utilize in zool etc. should be neat-clean. Height above 3.00 Mtr. To 6.00 Mtr.	1.00	Smt.	
8	Pillar less mandap (Dom Mandap) with zool on Ballies / Bamboos or iron pipe structure zool as directed in mandap etc. complete including necessary excavation fitting, above 16' ft height etc. complete as per instruction. The Zool and cloth should be used is neat and clean and good quality. (upto 90ft width)	1.00	Smt.	
9	Complete steel structure dome mandap upto 35' ft height with RCC foundation Base plate Nut-Bolt fitting complete structure with zool in selected cloth in ceiling. Top sided etc. as per instruction & requirement. The Zool and cloth should be used is neat and clean and good quality.including submission of the structural stability certificate for dome from Govt. approved structural engineer prior to function day to Engineer in charge. as directed by engineer in charge.	1.00	Smt.	
10	Complete steel structure dome mandap upto 35' ft height with RCC foundation Base plate Nut-Bolt fitting complete structure with zool in selected cloth in ceiling. In & Top (Double sided) etc. as per instruction & requirement. The Zool and cloth should be used is neat and clean and good quality.(150ft with) including submission of the structural stability certificate for dome from Govt. approved structural engineer prior to function day to Engineer in charge. as directed by engineer in charge.	1.00	Smt.	
11	Complete steel structure dome mandap upto 35' ft height with RCC foundation Base plate Nut-Bolt fitting complete structure with zool in selected inside cloth in ceiling.& Top side plastic / Tadptri (Water Proof) etc. as per instruction & requirement.	1.00	Smt.	
12	Complete steel structure dome mandap upto 35' ft height with RCC foundation Base plate Nut-Bolt fitting complete structure with zool in selected .In & Top side (Double sided)cloth and plastic or tadptri and net jali in ceiling. with water proof Mandap etc. as per instruction & requirement. including submission of the structural stability certificate for dome from Govt. approved structural engineer prior to function day to Engineer in charge. as directed by engineer in charge.	1.00	Smt.	
13	Providing selected cloth and jute flooring or green net flooring with different color as per instruction & requirement. and destory the debris and grad and leveling of the ground. The Zool and cloth should be used is neat and clean and good quality.	1.00	Smt.	
14	Providing selected cloth and P.V.C. net flooring on stage and on floor as per instruction & requirement. and destroy the debris and gradd and leveling of the ground.	1.00	Smt.	
15	Providing Stage having shape of Square / Rectangular / Round including flooring of Kantan / Green Net / Cloth with wooden steps including cloth zool around the stage. The Zool and cloth should be used is neat and clean and good quality.(A) Up to 1 Mtr. Height	1.00	Smt.	
16	Providing Stage having shape of Square / Rectangular / Round including flooring of Kantan / Green Net / Cloth with wooden steps including cloth zool around the stage. The Zool and cloth should be used is neat and clean and good quality.(B) Upto 1 to 1.5 Mtr. Height	1.00	Smt.	
17	Providing Stage having shape of Square / Rectangular / Round including flooring of Kantan / Green Net / Cloth with wooden steps including cloth zool around the stage. The Zool and cloth should be used is neat and clean and good quality.(C) Up to 1.5 to 3.0 Mtr. Height	1.00	Smt.	

18	Providing Stage back screen Wall of wooden or M.S. framing covering good approved color & quality shartin cloth providing proper wooden or M.S. supports for stability etc. complete as directed. The satin cloth should be used is neat and clean and good quality.(A) Up to 3 Mtr. Height.	1.00	Rmt.	
19	Providing Stage back screen Wall of wooden or M.S. framing covering good approved color & quality shartin cloth providing proper wooden or M.S. supports for stability etc. complete as directed. The satin cloth should be used is neat and clean and good quality.(A) Up to 3 Mtr. Height (Both side).	1.00	Rmt.	
20	Providing Stage back screen Wall of wooden or M.S. framing covering good approved colour & quality shartin cloth providing proper wooden or M.S. supports for stability etc. complete as directed. The satin cloth should be used is neat and clean and good quality. (B) Above 3 Mtr. Height.	1.00	Smt.	
21	Providing Stage back screen Wall of wooden or M.S. framing covering good approved color & quality shartin cloth providing proper wooden or M.S. supports for stability etc. complete as directed. The satin cloth should be used is neat and clean and good quality. (B) Above 3 Mtr. Height (Both side).	1.00	Smt.	
22	Providing plywood stage flooring in square / rectangle / or any shape complete as directed. avg 8 to 12 mm thick	1.00	Smt.	
23	Providing plywood stage flooring in square / rectangle / or any shape complete as directed. avg 19 mm thick	1.00	Smt.	
24	Providing selected Color cloth Kachi Wall around shamiyana, etc. complete as directed. The cloth utilise in wall	1.00	Rmt.	
25	Providing selected Color cloth Kachi Wall around shamiyana, etc. complete as directed. The cloth utilise in wall should be neat and clean and good quality. (B) Height above 1.85 Mtr.	1.00	Rmt.	
26	Providing wooden Framing wall Vertical support of M.S. or wooden member all four Side wooden batten patti (2" x 1/2" size) framing fixing fancy cloth / kantan including providing decorative Gamthi Toran or Sartin zool on top of wall etc. complete as directed. The cloth utilise in wall should be neat and clean and good quality.(A) Height up to 1.85 Mtr. One side cloth wall.	1.00	Rmt.	
27	Providing wooden Framing wall Vertical support of M.S. or wooden member all four Side wooden batten patti (2" x 1/2" size) framing fixing fancy cloth / kantan including providing decorative Gamthi Toran or Sartin zool on top of wall etc. complete as directed. The cloth utilise in wall should be neat and clean and good quality.(B) Height upto 1.85 Mtr. & both side Cloth wall.	1.00	Rmt.	
28	Providing wooden Framing wall Vertical support of M.S. or wooden member all four Side wooden batten patti (2" x 1/2" size) framing fixing fancy cloth / kantan including providing decorative Gamthi Toran or Sartin zool on top of wall etc. complete as directed. The cloth utilize in wall should be neat and clean and good quality.(C) Height above 1.85 Mtr. & 3 Mtr. One side Cloth wall.	1.00	Rmt.	
29	Providing wooden Framing wall Vertical support of M.S. or wooden member all four Side wooden batten patti (2" x 1/2" size) framing fixing fancy cloth / kantan including providing decorative Gamthi Toran or Sartin zool on top of wall etc. complete as directed. The cloth utilise in wall should be neat and clean and good quality.(C) Height above 1.85 Mtr. & 3 Mtr. Both side Cloth wall.	1.00	Rmt.	
30	Providing Box type Designed Gate(15' x 12' x 2') of wooden framing covering all four Side selected shartin cloth Providing required support for proper stability etc complete as directed of size 10' wide and 8' height.	1.00	No.	
31	Fancy Decorative Gate (Full size) ring / triangle / square / rectangle above 15 ft height including necessary fitting, framing, etc. Complete. as per requirement and instruction.	1.00	No.	
32	Providing Fancy Patti Gate.	1.00	No.	
33	Providing Fancy partition Gate.	1.00	No.	
34	Providing Fancy round Gate (Ring Gate).	1.00	No.	
35	Providing Red Carpet ro any color as per instruction.	1.00	Smt.	
36	Providing Coir mat Carpet.	1.00	Smt.	
37	Providing Jute Mat Carpet (Full Size).	1.00	Smt.	
38	Providing Gadi gadla with cover (6' x 3').	1.00	No.	
39	Supply of wooden Molded Chair neat and clean and good quality. as per the instruction of Engineer-in-charge.	1.00	No.	
40	Supply of Steel Molded Chair neat and clean and good quality. as per the instruction of Engineer-in-charge.	1.00	No.	
41	Supply Plastic Molded Chair neat and clean and good Quality. as per the instruction of Engineer-in-charge. 0 to 10000 Chairs	1.00	No.	
42	Supply Plastic Molded Chair Red and Blake for VVIP/VIP cleaning and arranging on site as per the instruction of Engineer-in-charge.	1.00	No.	
43	Supply Wooden Decorative Chair neat and clean and good quality with U-Form Sit (V.V.I.P.)	1.00	No.	
44	Providing SS Frame and wooden chair for Press / Media persons with cushion including arranging on site as per the instruction of Engineer-in-charge.	1.00	No.	
45	Supplying Three Seat Sofa Shankheda Brass ,Alluminium or steel framing with small pillow neat and clean and good quality etc. complete with Siphon Cover.	1.00	No.	

46	Supplying Two Seat Sofa Shankheda Brass Alluminium or steel framing with small pillow neat and clean and good quality etc. complete with Siphon Cover.	1.00	No.	
47	Supplying One Seat Sofa Shankheda Brass Alluminium or steel framing with small pillow neat and clean and good quality etc. complete with Siphon Cover.	1.00	No.	
48	Supplying good quality One Seater Soft in Leather or Good Quality Tapestry with small pillow for V.V.I.P.S.	1.00	No.	
49	Supplying good quality Two Seater Soft in Leather or Good Quality Tapestry with small pillow for V.V.I.P.S.	1.00	No.	
50	Supplying good quality Three Seater Soft in Leather or Good Quality Tapestry with small pillow for V.V.I.P.S.	1.00	No.	
51	Providing 1 Mtr. Height Dedo Wall with both side cloth and Framing of Wooden / Steel using Weld mesh Jali, etc.complete.	1.00	Rmt.	
52	Galvanized good quality Corrugated Sheets 0.8mm thick fixing required height up to wall with framing in Wooden /Steel etc. complete.	1.00	Sqm	
53	Bearcat with 6 percent or any other P.V.C. pipe in horizontal 3 lines height pipe support fitting etc. complete as per requirements Instruction.	1.00	Rmt.	
54	Bearcat in steel / All minimum Checkered grill fitted with 3 to 4.00 feet height with pipe support fitting / Wooden etc. complete as per requirement. & Instruction.	1.00	Rmt.	
55	Barrel for Water (Nala) 200 Ltr. Capacity (A) Galvanized./Aluminum / Brass / Iron / Steel / PVC	1.00	No.	
56	Supplying of branded ISI mark Mineral water bottle as per instruction of engineer in charge 100 ml	1.00	No.	
57	Supplying of branded ISI mark Mineral water bottle as per instruction of engineer in charge 250 ml	1.00	No.	
58	Supplying of branded ISI mark Mineral water bottle as per instruction of engineer in charge (Himalaya Only) 500 ml	1.00	No.	
59	Supplying of branded ISI mark Mineral water bottle as per instruction of engineer in charge (Himalaya Only) 1000 ml.	1.00	No.	
60	Supplying of branded ISI mark Mineral water bottle as per instruction of engineer in charge (Himalaya Only) 250 ml.	1.00	No.	
61	VVIP Glass Teapoi.	1.00	No.	
62	Supplying and Fixing Wash Basin - Simple	1.00	No.	
63	Supplying Sintex tube	1.00	No.	
64	Supplying Steel tube	1.00	No.	
65	Supplying Seating Counter using Round Table with 10 person Capacity. The table cloth and Jool should be good quality.etc complete	1.00	No.	
66	Providing and fixing Green Room plywood structure with required design and 18 mm thickness of plywood sheets with all material transportation scaffolding labour, required necessary gap etc complete.	1.00	SqFt.	
67	Providing & fixing green room at various location with minimum size 20ft. X 15ft and maximum size up to 40ft x 15ft as directed with minimum 12ft height with waterproof top all side covering with zool and red carpet on total floor with entarance door facilities for VIP and partition wall of PVC / Alluminium Partion wall of flexible units for toilet facilities aircraft toilet(chemical toilet), washbasin, with all facilities like water tank, drainage facilities, towel - rod, washbasin bibcooks, pillar cooks, flash cooks, mirror, napkins, paper napkins, air freshners, toilet freshners with VVIP seating arrangement for 10 persons including good quality of sofasets, VIP cushion chairs, side tipoy, central tipoy with all labours materials as directed by Engineer in charge etc. comp.	1.00	No.	
68	Providing and fixing Gree Room required wooden planck frame for plywood with required design and thickness of plywood sheets with all material transportation scaffolding labour etc complete	1.00	SqFt.	
69	Moulded Aircraft type VIP Toilets /Chemical toilet with European Seat, Looking Glass and arrangement of Water tank, Stands and soakpits.	1.00	No.	
70	Prov. Jute Urinals block complete for public (Each block have 10 units) at function place & parking place with mandap and sinages with all labour & materils as directed by engineer in charge as directed etc. comp.	1.00	No.	
71	Making the surface level & dustproof, providing & fixing 6mm Thk. Model -SPLENDOUR - 100% BCF Polypropylene Carpet to be fixed on walls and floors. The rates shall include cost of all types of labor, material, transportation, etc. complete. (equivalent Brand DIVINE)	1.00	Sqm	
72	Providing Rostam having 10 ft. height using M.S. pre fabricated frame of M.S. pipe/ angle/ channel with cross bracing and wooden top, 19 mm plywood flooring and cloth zool covering three sides of Rostam and back side covered with G.C.I. sheet with M.S. Framing Providing Zool railing and stair steps etc complete as directed.	1.00	1 Smt. (Floor Area)	
73	Providing Table cloth and zool up to 1 mt. height.	1.00	No.	
74	Providing Ramp constructing and fixing ramp of any Size.	1.00	Smt.	
75	Providing Tepoy good quality (Glass, Formica, Sankheda, wooden, steel etc.)	1.00	No.	
76	Providing Necessary pipe line fitting for disposing Rain water from Mandap.	1.00	Rmt.	
77	Providing Chiffon cloth with chair cover (As per instructed Symbol).	1.00	No.	

78	Providing and fixing MOJO type barricade made from M.S. Angel Frame with G.I. Wire mesh jail of required height on hire charge including dismantling the same after completion of the event including all transportation, carriage, lead and lift etc. complete as directed by engineer in charge.	1.00	Rmt.	
79	Providing Flag various color required logo in pipe at road site including fitting etc. complete as per site condition and as directed by Engineer-in-charge.	1.00	No.	
80	Providing Steel frame powder coated leather V.V.I.P chair set with back side cushion and cover.	1.00	No.	
81	Providing Designer Gate of necessary steel structure with cotton cloth cover all side with selected in any shape. of any height & site as per instruction of higher officers, Engineer-in- charge and site requirement.	1.00	No.	
82	Providing Decorative railing in both side stage & front of stage & both side of steps with coloured cloth covering as per instructions & requirement etc. comp. (A) Iron Railing.	1.00	Rmt.	
83	Providing Decorative railing in both side stage & front of stage & both side of steps with coloured cloth covering as per instructions & requirement etc. comp. (B) Wooden Railing.	1.00	Rmt.	
84	Providing Decorative railing in both side stage & front of stage & both side of steps with coloured cloth covering as per instructions & requirement etc. comp. (C) Steel or Brass Railing.	1.00	Rmt.	
85	Providing & Fixing Faciya.	1.00	Smt.	
86	Providing Multi Level Stage with steps/ramps of as required height for dignitaries constructed with using pre-fabricated steel 'H' framed, supported Ghoda with square / round steel plate welded at bottom of H-Frame pipe for levelling and cross bracing each steel pipe member fixed properly with special Cup lock clamps on both side. The top has to be covered with 19mm thick Double layer Plywood in proper level and providing Fresh Red synthetic carpet flooring on stage steps and covering the cloth zool to four sides etc. complete as per site condition and instruction of Engineer-in- charge.(A) Stage upto 1.5 Mtr. Height.	1.00	Smt.	
87	Providing Multi Level Stage with steps/ramps of as required height for dignitaries constructed with using pre-fabricated steel 'H' framed, supported Ghoda with square / round steel plate welded at bottom of H-Frame pipe for levelling and cross bracing each steel pipe member fixed properly with special Cup Lock clamps on both side. The top has to be covered with 19mm thick Double layer Plywood in proper level and providing Fresh Red synthetic carpet flooring on stage steps and covering the cloth zool to four sides etc. complete as per site condition and instruction of Engineer-in- charge.(B) Stage upto 4.0Mtr. Height.	1.00	Smt.	
88	Providing Multi Level Stage with steps/ramps of as required height for dignitaries constructed with using pre-fabricated steel 'H' framed, supported Ghoda with square / round steel plate welded at bottom of H-Frame pipe for levelling and cross bracing each steel pipe member fixed properly with special Cup Lock clamps on both side. The top has to be covered with 19mm thick Double layer Plywood in proper level and providing Fresh Red synthetic carpet flooring on stage steps and covering the cloth zool to four sides etc. complete as per site condition and instruction of Engineer-in- charge.(C) Stage upto 4.00 Mtr. Height.	1.00	Smt.	
89	Providing Multi Level Stage with steps/ramps of as required height for dignitaries constructed with using pre-fabricated steel 'H' framed, supported Ghoda with square / round steel plate welded at bottom of H-Frame pipe for levelling and cross bracing each steel pipe member fixed properly with special Cup Lock clamps on both side. The top has to be covered with 19mm thick Double layer Plywood in proper level and providing Fresh Red synthetic carpet flooring on stage steps and covering the cloth zool to four sides etc. complete as per site condition and instruction of Engineer-in- charge.(C) Stage upto 6.00 to above Mtr. Height.	1.00	Smt.	
90	Providing Wooden 2" to 3" Thick long Bamboo / Ballies using cross Bressing Mandap frame on Tadpatri/ Thick Plastic including fitting complete structure of water proof Mandap with Zool Patta. including necessary excavation fitting, up to 16' height etc. comp. as per instruction.	1.00	Rmt.	
91	Providing Complete Steel Structure dome or tringular hanger type Mandap with RCC Foundation Base Plate, Nut-Bolt Fitting complete with zool in selected cloth in ceiling upto 14 ft. height.	1.00	Smt.	
92	Providing Pillar less Mandap Iron Pipe Structure as directed in mandap upto 14 ft. height.	1.00	Smt.	
93	Supplying and fixing of Wooden Ramp of 19mm thick plywood having up to 4 Ft. wide with good quality wooden frame including necessary bracing and support made on site with Red carpet including 3 ft. height wooden Railing on both side of Ramp with necessary clothing, etc. as per the instruction and site requirement.(A) upto 1.50 Mtr. height	1.00	Rmt.	
94	Supplying and fixing of Wooden Ramp of 19mm thick plywood having upto 4 Ft. wide with good quality wooden frame including necessary bracing and support made on site with Red carpet including 3 ft. height wooden Railing on both side of Ramp with necessary clothing, etc. as per the instruction and site requirement.(B) up to 4.00 Mtr. height.	1.00	Rmt.	
95	Supplying and fixing of Wooden Ramp of 19mm thick plywood having up to 4 Ft. wide with good quality wooden frame including necessary bracing and support made on site with Red carpet including 3 ft. height wooden Railing on both side of Ramp with necessary clothing, etc. as per the instruction and site requirement.(C) upto 6.00 Mtr. and above height.	1.00	Rmt.	
96	(A) Steel / SS Frame with Leather Seat Back Chair including cleaning and arranging on site as per the instruction of Engineer-in-charge.	1.00	No.	
97	Providing Dias Table with Table Cloth and Zool. The Cloth and zoll should be neat and clean and good quality.	1.00	No.	
98	Providing Sound Stage as per required height.	1.00	No.	
99	Providing and Fixing Wire mesh Jali.	1.00	Smt.	

100	Providing multi level display center as per requirement in size i.e. (Height width and length) with proper steel H flames.	1.00	Smt.	
101	Providing Water proof screen Side & Back Side in German Aluminum Dome as per requirement. The water proof Screen is good quality and neat and clean.	1.00	Smt.	
102	Providing and Fixing Sofa Cover for Good Quality.	1.00	Nos	
103	Providing truss Mandap with necessary truss framing and selected cloth in roof & covering for truss.	1.00	Smt.	
104	Complete Real Flower Decoration, for Front and Sides, Backdrop, Welcome Gate, Elevated Pathway, Stage Railing, Stair Railing, Podium, Khat Muhurat Place, Under LED Screen, On Tipoi with real flower sur, flower belt, flower toran with 3 to 5 sur & bouquet as required.	1.00	Rmt.	
105	Providing & Erecting Tin Shed, prefab Steel+A3 Structural framework consisting of 2" M.S. pipe vertical poles, 2" M.S. pipe rafters and 2" Purins, having roof 24 gauge galvanized sheet covered with Talpore/Agro net. Bottom of GI sheet covered with net & Clean cloth ceiling. all steel structure member painted with enamel paint. height of shed various from 12 to 20 feet as per instruction of Engineer in Charge.	1.00	Sqm	
106	19mm Block Board platform properly laid on wooden Section Framework raised 4" to 9" above the ground in proper line and level VIP sitting area on both side.	1.00	Sqm	
107	Elevated pathway required with leading to the flag platform to be constructed using prefabricated H Frame Supports in 2"M.S. pipe having height up to 3 to 5 feet with cross members fixed properly for stability. the top has to be covered with 18mm Block Board or plywood in proper level. including top & all four side of stage covered with neat & clean cloth as directed by Engineer in Charge.	1.00	Sqm	
108	Providing and fixing wooden barricade having height 4 to 5 feet by using vertical poles and two horizontal wooden member or G.I. Pipe tied with vertical poles including making 0.45cm deep pit to fix the vertical pole including warping the cloth to vertical and horizontal pole etc. complete.	1.00	Rmt.	
109	Decorating Flags in Satin Cloth fixed on 2" M.S. pipe properly painted. Having height 15 to 20 feet as per directed of Engineer in charge.	1.00	No	
110	Providing & Fixing wooden tables covered top & sides by decorative cloth.	1.00	No	
111	Fixing all types of Flax / Banner of any size at place as directed by engineer in charge.	1.00	No	
112	M.S. Pipe Barricading with M.S. channel / Pipe vertical & horizontal supports properly bolted with painting in silver color as directed by engineer in charge.	1.00	Rmt.	
113	Supply & installing of DCP Type - 5 Kg. Capacity Fire Extinguisher as per IS-2171 I.S.I mark with necessary fittings etc. Complete.	1.00	No	
114	Supply & installing of Water Co2 Type - 9 Ltr. Capacity FireExtinguisher as per IS. A.I.S.I. Mark with necessary fittings etc. Complete	1.00	No	
115	Preparing colorful cloth decoration (leria) Draping in Dome & Cloth Partition as directed on cloth wall using satin colorful work including all labors and material, design as per directed.	1.00	Sqm	