

BHAKTA KAVI NARSINH MEHTA UNIVERSITY, JUNAGADH

[Gujarat Public Universities Act No. 15/2023]

Government Polytechnic Campus, Bhakta Kavi Narsinh Mehta University Road,
Khadiya, Junagadh-362263 (Gujarat)

Ph: 0285-2681400 : www.bknmu.edu.in || M store@bknmu.edu.in

જાહેરાત

તા.૦૬/૦૭/૨૦૨૬

આથી જાહેરાત આપવામાં આવે છે કે, ભક્તકવિ નરસિંહ મહેતા યુનિવર્સિટી જુનાગઢના ન્યુ કેમ્પસ ખાતે કેમેસ્ટ્રી તથા લાઈફ સાયન્સ વિભાગ માટે પાણીના બોર તથા તેને અનુસંગિક કામગીરી કરવા માટે તથા અન્ય વિભાગો માટે કેબલ, બોરની સબમર્સીબલ મોટર તથા પાઈપ લાઈન સપ્લાય કરી ફીટ કરવા માટે જુદી-જુદી એજેન્સી પાસેથી સીલ બંધ કવરમાં આર.પી એડી થી પાંચ લાખની મર્યાદામાં ભાવો મંગાવવામાં આવેલ છે. જે દિન - ૦૫ માં જરૂરી વિગત સાથે ભક્તકવિ નરસિંહ મહેતા યુનિવર્સિટી, ખડિયા, જુનાગઢ ને પહોંચતા કરવાના છે. આ સાથે કરવાની થતી કામગીરીની વિગતો સામેલ રાખેલ છે.

સીનીયર એન્જીનીયર(સિવિલ)

ક્રમાંક/બીકેએનએમયુ/બાંધકામ/૧૩૫/૨૦૨૬-૨૭

તા.૦૬/૦૭/૨૦૨૬

-:શરતો:-

- સંપૂર્ણ કામગીરી ટેન્ડરમાં દર્શાવેલ શરતો મુજબ કરી આપવાની રહેશે.
- સંપૂર્ણ કામગીરી યુનિવર્સિટીના સીનીયર એન્જીનીયરશ્રી(સિવિલ) ના સુચના મુજબ કરવાની રહેશે.
- કામગીરી કર્યા બાદ યુનિવર્સિટી સીનીયર એન્જીનીયર(સિવિલ) પાસે ચેક કરાવાની રહેશે.
- કામગીરી પૂર્ણ કર્યા બાદ સાઈટ પરના એક્ઝ્યુઅલ મેઝરમેન્ટ પ્રમાણે બીલની ગણતરી કરવામાં આવશે.
- આપના દ્વારા બીલ રજૂ થયેલ થી ૦૧ માસ માં બીલની ખરાઈ કરી ચુકવણું કરવામાં આવશે.
- કામગીરી દરમિયાન જે મશીનરી તથા લેબરની જરૂરિયાત રહેશે તે આપના દ્વારા કરવાની રહેશે.
- ટેન્ડરમાં દર્શાવેલ આઈટમની ખરીદી સીનીયર એન્જીનીયર(સિવિલ) ની સુચના તેમજ મેક-લીસ્ટ મુજબ કરવાની રહેશે.

NAME OF WORK :- Drilling bore with necessary accessory for Life-Sci and Chemistry Building at New Campus			
Sr. No	Quantity	Description of Item	Unit
1	60.00	Drilling of 200 / 215 mm dia. bore hole in overburden strata by DTH rig up to required depth including fixing of 175 / 180 dia MS ERW/ PVC casing pipe & further drilling of 165 mm dia. bore hole in hard rock (trap etc.) strata by DTH drilling method up to total depth of 300 meters including measuring the yield by V notch and flushing of bore etc. complete in all districts of Zone V. (Casing up to 12 MTS.) From 0 mts to 60mts MR.	Rmt.
2	90.00	Drilling of 200 / 215 mm dia. bore hole in overburden strata by DTH rig up to required depth including fixing of 175 / 180 dia MS ERW/ PVC casing pipe & further drilling of 165 mm dia. bore hole in hard rock (trap etc.) strata by DTH drilling method up to total depth of 300 meters including measuring the yield by V notch and flushing of bore etc. complete in all districts of Zone V. (Casing up to 12 MTS.) From 60 mts to 150 mts MR.	Rmt.
3	70.00	Drilling of 200 / 215 mm dia. bore hole in overburden strata by DTH rig up to required depth including fixing of 175 / 180 dia MS ERW/ PVC casing pipe & further drilling of 165 mm dia. bore hole in hard rock (trap etc.) strata by DTH drilling method up to total depth of 300 meters including measuring the yield by V notch and flushing of bore etc. complete in all districts of Zone V. (Casing up to 12 MTS.) From 150 mts to 225 mts MR.	Rmt.
4	4.00	Supplying and Erecting 3-Phase Borewell Submersible Pump Sets (Electric motor driven borewell submersible pump set confirming to IS 8034 and motor confirming to IS 9283 working at 3 phase 400 / 440 volt 50 Hz AC supply & 2900 RPM) Discharge 180 LPM, Head 108 mt, 10HP MR.	Nos.


 Senior Engineer (Civil)
 Bhakta Kavi Narsinh Mehta University
 Junagadh.